



NOTES

1. NEW PAVEMENT THICKNESS SHALL BE EXISTING PLUS ONE INCH (P+1"), BUT NOT LESS THAN EIGHT INCHES (8").
2. PERMANENT PAVING SHALL BE COMPLETED WITHIN FIVE (5) DAYS AFTER EXCAVATION. TEMPORARY PAVING SHALL BE TWO-INCH (2") MINIMUM HOT MIX.
3. TRENCH PAVING CUT AREAS SHALL BE SEALED WITH SS 1-H ASPHALTIC EMULSION AT THE RATE OF 0.08 TO 0.10 GALLON PER SQUARE YARD, NOT SOONER THAN 24 HOURS AFTER PLACEMENT OF PAVEMENT.
4. STREET SURFACE SHALL BE SEALED WITH AN EMULSION AGGREGATE SLURRY AS DETERMINED BY THE INSPECTOR.

CITY OF DOWNEY - DEPT. OF PUBLIC WORKS - ENGINEERING DIVISION

TRENCH PAVING SECTION
- CONDUIT -

DESIGNED BY: E.E.	VERT. SCALE
DRAWN BY: E.P.	HORIZ. SCALE
CHECKED BY: E.E.	SHEET 1 OF 1 SHEETS
APPROVED BY: _____ CITY ENGINEER	DWG. NO. _____